Published: 16-Apr-2012 Roof Opening Panel - Roof Opening Panel

Diagnosis and Testing

Principle of Operation

For a detailed description of the roof opening panel system and operation, refer to the relevant Description and Operation section of the workshop manual. REFER to: (501-17 Roof Opening Panel)

Roof Opening Panel (Description and Operation), Roof Opening Panel (Description and Operation), Roof Opening Panel (Description and Operation).

Inspection and Verification

CAUTION: Diagnosis by substitution from a donor vehicle is **NOT** acceptable. Substitution of control modules does not guarantee confirmation of a fault and may also cause additional faults in the vehicle being checked and/or the donor vehicle.

- 1. Verify the customer concern.
- 2. Visually inspect for obvious signs of damage and system integrity.

Visual Inspection

Mechanical	Electrical
 Glass panel assembly Glass panel seal Frame assembly Roller blind(s) Deflector Access panel Roof opening panel cables 	 Fuses Battery Junction Box (BJB) Central Junction Box (CJB) Wiring harness Loose or corroded connector(s) Roof opening panel motor and control module Roof opening panel switch

3. If an obvious cause for an observed or reported concern is found, correct the cause (if possible) before proceeding to the next step.

4. If the cause is not visually evident verify the symptom and refer to the Symptom Chart, alternatively check for Diagnostic Trouble Codes (DTCs) and refer to the DTC Index.

Symptom Chart

Symptom	Possible Cause	Action
Roof opening panel inoperative	 Roof opening panel calibration lost Fuse(s) blown Control circuit fault Supply circuit fault Motor fault 	 Calibrate the roof opening panel REFER to: <u>Motor Synchronization</u> (501-17 Roof Opening Panel, General Procedures). Check the fuse(s) Check the roof opening panel circuits Carry out hard battery reset Check the switch and motor function
Roof opening panel creak	 Contact between sunroof frame seal and vehicle body Sunroof frame twist Moving panel contact to sunroof frame Ice formation between the body and sunroof 	• GO to Pinpoint Test <u>F.</u>
Roof opening panel sticking or juddering	 Debris in the channels/guides Cable(s) sticking/damaged Roof opening panel incorrectly aligned Switch fault Motor fault 	 Check for general debris Inspect, clean and lubricate the cable(s) and guides Check the roof opening panel alignment. REFER to: <u>Roof Opening Panel Alignment</u> (501-17 Roof Opening Panel, General Procedures). Check the switch and motor function
	 Debris in the channels/guides Damage to the glass panel seal 	 Check for general debris Inspect, clean and lubricate the cable(s) and guides Check the glass panel seal

Water ingress from roof opening panel	 Roof opening panel incorrectly aligned Failed bond of sunroof frame to body Failed bond of fixed glass panels to sunroof frame 	 Check the roof opening panel alignment REFER to: <u>Roof Opening Panel Alignment</u> (501-17 Roof Opening Panel, General Procedures).
Roof opening panel blind - gap to headliner	 Miss-alignment of blind closing position Broken / incorrectly installed headliner clips 	• GO to Pinpoint Test <u>A.</u>
Roof opening panel blind noise	 Broken / incorrectly installed blind feet Warped blind drive mechanism casting Blind spring rattle 	• GO to Pinpoint Test <u>B.</u>
Wind noise	 Damage to the glass panel seal Cable(s) sticking/damaged Roof opening panel incorrectly aligned 	 Check the glass panel seals Inspect, clean and lubricate the cable(s) and guides Check the roof opening panel alignment REFER to: <u>Roof Opening Panel Alignment</u> (501-17 Roof Opening Panel, General Procedures).

DTC Index

For a list of Diagnostic Trouble Codes (DTCs) that could be logged on this vehicle, please refer to Section 100-00. REFER to: <u>Diagnostic Trouble Code (DTC) Index - DTC: Central Junction Box (BCM)</u> (100-00 General Information, Description and Operation).

TEST CONDITIONS	DETAILS/RESULTS/ACTIONS
A1: BLIND OPERATION	
AI: BLIND OPERATION	1 Operate the roof opening panel blind from open to closed
	 Operate the roof opening panel blind from open to closed twice , using the console mounted switch
	Does the roof opening panel blind operate correctly?
	Yes
	GO to A2.
	No
	GO to Pinpoint Test B.
A2: BLIND TO HEADLINER GAP	
	Carry out a visual inspection of the condition of the closed blind to the headliner
	Is there an excessive or abnormal gap between the blind and
	headliner?
	Yes
	GO to A3 . No
	No further action required
A3: GAP ORIENTATION	
	Carry out a visual inspection of the condition of the closed blind to the headliner

E142515	
	Is the gap from the leading edge of the blind to the edge of the headliner in the X-direction (fore/aft)?
	Yes Calibrate the roof opening panel REFER to: Motor Synchronization (501-17 Roof Opening
	Panel, General Procedures). Then <u>GO to A4</u> .
	No Check headliner is correctly retained. Re-secure as required. If customer concern is still evident follow the procedure REFER to: <u>Headliner</u> (501-05 Interior Trim and Ornamentation, Removal and Installation). Replace the headliner clips. Then <u>GO to A5</u> .
A4: BLIND - FEET	1 Operate the roof opening panel blind from open to closed
	twice , using the console mounted switch 2 Carry out a visual inspection of the condition of the closed
	Is the customer concern still evident?
	Yes Carry out visual inspection of the blind feet for correct installation and damage, re-install or replace as required REFER to: <u>Roof Opening Panel Blind Feet</u> (501-17 Roof Opening Panel, Removal and Installation). Then <u>GO to A5</u> . No
A5: CLEARANCE APERTURE - VISUAL CHECK	No further action required
	1 Operate the roof opening panel blind from open to closed twice , using the console mounted switch
	2 Carry out a visual inspection of the condition of the closed blind to the headliner
	Is the customer concern still evident? Yes
	If customer concern is still evident contact dealer technical support No
PINPOINT TEST B : ROOF OPENING PANEL BLIND - M	No further action required OTOR – NOISE OR INOPERATIVE
TEST DETAILS/RESULTS/ACTIONS	
CONDITIONS B1: MOTOR OPERATION	
1 Operate the roof opening panel blind ι	ising the console mounted switch
Listen for noise that would indicate that	
Is there a noise generated when the blind a Yes	switch is pressed?
GO to B2.	
GO to Pinpoint Test <u>E.</u>	

B2: HIGH LEVEL	NOISE
	1 Operate the roof opening panel blind using the console mounted switch
	Does the blind make a loud ratcheting noise when the switch is pressed?
	Yes
	Replace the glass panel blind drive assembly (Front)
	REFER to: Roof Opening Panel Blind Drive Assembly (501-17 Roof Opening Panel, Removal and
	Installation).
	(Rear)
	REFER to: <u>Glass Roof Panel Blind Drive Assembly</u> (501-11 Glass, Frames and Mechanisms, Removal and
	Installation).
	No
	Carry out visual inspection of the blind feet for correct installation and damage, replace as required
	REFER to: <u>Roof Opening Panel Blind Feet</u> (501-17 Roof Opening Panel, Removal and Installation).
	Then GO to B3.
B3: HIGH LEVEL	- NOISE - CHECK
	1 Operate the roof opening panel blind using the console mounted switch
	Is the customer concern still evident?
	Yes
	If customer concern is still evident contact dealer technical support
	No
	No further action required
PINPOINT TES	T C : ROOF OPENING PANEL BLIND – NOISE
TEST	DETAILS/RESULTS/ACTIONS
CONDITIONS	
C1: BLIND - FEE	
	1 Operate the roof opening panel blind using the console mounted switch
	Is the noise only present during operation of the blind
	Yes
	Carry out visual inspection of the blind feet for correct installation and damage, replace as required, as
	per procedure
	REFER to: Roof Opening Panel Blind Feet (501-17 Roof Opening Panel, Removal and Installation).
	Then <u>GO to C2</u> .
	No
	GO to Pinpoint Test D.
C2: BLIND - RE	
	1 Operate the roof opening panel blind using the console mounted switch
	Is the customer concern still evident?
	Yes
	Re-tension the blind
	REFER to: Roof Opening Panel Blind Rewind Procedure (501-17 Roof Opening Panel, General
	Procedures).
	Then <u>GO to C3</u> .
	No
	No further action required
C3: REPLACEME	
	1 Operate the roof opening panel blind using the console mounted switch
	Is the customer concern still evident?
	Yes
	Replace the blind assembly
	REFER to: Roof Opening Panel Blind (501-17 Roof Opening Panel, Removal and Installation).
	Then <u>GO to C4</u> .
	No
	No further action required
C4: AUDIBLE NO	
	1 Operate the roof opening panel blind using the console mounted switch
	Is the customer concern still evident?
	Yes
	If customer concern is still evident contact dealer technical support
	No further action required
<u></u>	No further action required
PINPOINT TES	T D : ROOF OPENING PANEL BLIND – NOISE / RATTLE
TEST CONDITIO	NS DETAILS/RESULTS/ACTIONS
	EHICLE IN MOTION
	1 Verify the customer concern by performing a road test (Observe the road test safety guidelines)
	2 Check if the concern is evident with the blind in open and closed positions
	Is the noise present when the blind is closed?
	Yes
	Contact dealer technical support
	No
	GO to D2.

D2: RATTLE - VEF	IICLE IN MOTION
	1 Confirm the vehicle identification number
	Is the VIN number below V17000
	Yes
	Replace the blind assembly REFER to: <u>Roof Opening Panel Blind</u> (501-17 Roof Opening Panel, Removal and Installation).
	If customer concern is still evident contact dealer technical support
	No
	Contact dealer technical support
PINPOINT TEST	E : ROOF BLIND OPERATION
TEST DET.	AILS/RESULTS/ACTIONS
E1: OPERATION	
1	Operate the opening panel using the roof mounted switch
Doe	s the opening panel operate correctly?
Yes	
No	<u>GO to E2</u> .
	Refer to the electrical circuit diagrams. Check the fused links to the roof opening panel, roof blinds module
	and the front overhead console. Replace as required. If the fused link is intact refer to (roof opening panel)
	inoperative) in the symptom chart above
E2: VOLTAGE TO	BLIND MOTORS
\land	
	l motor + (red wire) should be at battery voltage during opening movement, blind motor – (black wire) ery voltage during closing movement
	Lower the headliner REFER to: Headliner (501-05 Interior Trim and Ornamentation, Removal and Installation).
	Front blind failure. Operate to roof blind switch. Refer to the electrical circuit diagrams check for voltage
	between connector - C9PR153A/5 - and - C9PR153A/1 -
3	Rear blind failure. Operate to roof blind switch. Refer to the electrical circuit diagrams check for voltage between connector - C9PR155A/1 - and - C9PR155A/5 -
	s the supply circuit operate as expected?
Yes	
	Suspect blind motor internal failure. Replace the glass panel blind drive assembly (Front) REFER to: Roof Opening Panel Blind Drive Assembly (501-17 Roof Opening Panel, Removal and
	Installation).
	(Rear)
	REFER to: Glass Roof Panel Blind Drive Assembly (501-11 Glass, Frames and Mechanisms, Removal and
	Installation).
No	<u>GO to E6</u> .
	<u>GO to E3</u> .
E3: SENSOR AND	SUPPLY CIRCUIT CHECKS
1	Front blind failure. Refer to the electrical circuit diagrams check the circuit for continuity and for short to
	power, ground or open circuit between connectors - C9PR32A - and - C9PR153A -
2	Rear blind failure. Refer to the electrical circuit diagrams check the circuit for continuity and for short to power, ground or open circuit between connectors - C9PR32A - and - C9PR155A -
Did	the circuit pass the tests?
Yes	
	<u>GO to E4</u> .
No	Panair or replace the blind barness. Then CO to EC
E4: SWITCH CIRC	Repair or replace the blind harness. Then GO to E6 .
	Refer to the electrical circuit diagrams check the circuit for continuity and for short to power, ground or
	open circuit between connectors - C9PR32A - and - C9LN28 -
í – í	the circuit pass the tests?
Yes	
N 1	<u>GO to E5</u> .
No	Repair or replace the switch circuit harness. Then GO to E6.
E5: SWITCH PACK	
	l circuit operation (one touch), a ground is supplied while the switch is pressed
	Refer to the electrical circuit diagrams and monitor voltage on the blind open / close circuits as the switch
	is pressed the switch circuits pass the tests?
Yes	
	GO to E6.
No	

	If the blind operation is the only fault suspect the front overhead console switch replace as required. Then GO to EG .
E6: CORRECT OP	
1	Operate the moving panel using the roof mounted switch
	s the moving panel operate correctly?
Yes	No further action required
No	If customer concern is still evident contact dealer technical support
PINPOINT TEST	F : ROOF OPENING PANEL - FRAME CREAK
TEST	DETAILS/RESULTS/ACTIONS
CONDITIONS F1: NOISE - WHE	J N PANEL IN VENT POSITION
$\overline{\wedge}$	se tests are to be carried out to determine the cause of the sunroof based creak noises
	Verify the customer concern by performing a road test (Observe the road test safety guidelines)
	2 Determine if the issue is present:
	When the opening panel is in the vent position
	When the opening panel is in the closed position
	On flat roads
	• When the car is under torsion (e.g. driving slowly up a curb, or turning onto an inclined drive-way)
	Is the noise present when the sunroof panel is in the vent position? Yes
	GO to F2.
	GO to Pinpoint Test G.
2: NOISE - WHE	N VEHICLE UNDER TORSION
	1 Using the results obtained
	Is the noise present on flat roads as well as when the vehicle is under torsion?
	Yes
	No GO to F3 .
F3: VIN RANGE	
	1 Check the vehicle VIN (vehicle identity number).
	Is vehicle VIN below V25000 ?
	Yes
	<u>GO to F4</u> . No
	Contact dealer technical support
-4: FRAME WASH	
	Operate the roof opening panel using the roof mounted switch to the fully open position
	2 Carry out visual inspection of the front corners fixings to confirm the presence of the frame washers
	Are the frame washers present?
	Yes Contact dealer technical support
	No Install frame washers REFER to: (501-17 Roof Opening Panel)
	Roof Opening Panel Frame Washers - Front (Removal and Installation),
	Roof Opening Panel Frame Washers - Centre (Removal and Installation),
	Roof Opening Panel Frame Washers - Rear (Removal and Installation).
	If the customer concern is still evident contact dealer technical support
F5: REAR PANEL	SEAL LUBRICATION
	Lubricate the rear fixed panel seal REFER to: <u>Rear Glass Roof Panel Lubrication</u> (501-11 Glass, Frames and Mechanisms, General Procedures).
	Is the customer concern still evident?
	Yes Contact dealer technical support
	No No further action required
PINPOINT TEST	G : ROOF OPENING PANEL - GLASS PANEL CREAK
TEST CONDITION	S DETAILS/RESULTS/ACTIONS
G1: GLASS PANE	
	IΠ

G2: MECHANISM - CLEARANCE TO FRAME	opening panel alignment. REFER to: <u>Roof Opening Panel Alignme</u> Opening Panel, General Procedures). a profile correct? <u>GO to G2</u> . Check the roof opening panel alignmer REFER to: <u>Roof Opening Panel Alignme</u> Opening Panel, General Procedures). <u>f the concern persists, GO to G2</u> .	t
	Remove the side covers from the glass	nanel
Image: wide state	With the glass panel in the tilt position nspection of the mechanism clearance eft and right side of the vehicle	carry out a visual
	the mechanism contact the frame?	
	Contact dealer technical support	
	<u>GO to G3</u> .	
G3: MECHANISM ARM CREAK		
	Remove the moving glass panel REFER to: <u>Roof Opening Panel Glass</u> (5 Panel, Removal and Installation).	
	Close the mechanism and gently flex the nechanism arm inboard – both left sid	
	this produce a creaking noise?	
	f customer concern is still evident con support	act dealer technical
	GO to G4 .	
G4: DEBRIS IN WIND NOISE SEAL		
	Compress the side wind noise seals ald heck for any debris contaminating the	
	ere any debris?	
	Remove any debris from the section ar suitable tool inside the seal <u>GO to G5</u> .	ea by sliding a
	GO to G5	
G5: MOVING PANEL SEAL LUBRICATION		
	Clean all moving panel seals using a da	
	Apply AC602/2 lubricant to the all mov a suitable clean cloth	ing panel seals using
	e customer concern still evident?	
	f customer concern is still evident con	act dealor tochnical
	support	

No further action required